

LIGHT HOUSE PROJECT LUCKNOW, UTTAR PRADESH



Construction Agency: M/s JAM Sustainable Housing LLP

No of Houses :	1,040
Technology :	Stay In Place PVC Formwork with Pre-Engineered Steel Structural System
Origin :	Canada
No of Towers :	4
No of Floors :	S+13
Project Cost :	₹ 130.90 Cr.
Built up area :	47,826.6 sqm
Social Infra :	Community centre, Commercial centre

Special features : Easy to erect the wall panels requiring no plaster, dust free environment, Solar lighting, Rain Water Harvesting, STP

Construction Process

- 1 Customised steel columns & beams manufactured in the factory are erected at site
- 2 Deck slab installation in already erected steel structure & Concreting with services
- 3 Factory made prefinished PVC Wall forms are installed as infilled walls along with services
- 4 Filling of infill walls with concrete



The Light House Project, Lucknow is in finishing stage.



Location: Near Awadh Ship Gram, Sec - 5, Awadh Vihar Yojana, Lucknow (U.P)